BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2022-23 Dated:10-08-2022

APPROVED TENDER SCHEDULE –'B'

Item 16

Name of Work:-Maintennce of Ganesh immersion tank at Allalasandra Kalyani in ward no:05 Yelahanka New Town Sub Division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri PRASHANTH M (MARADIS ENTERPRISES)	
				Rate	Rate in Words
1	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work . Loading and Unloading of Stone Boulder/Stone aggregates /Sand/Kankar/Moorum.(Tipper 5.5 m3) Removal of Silt in Kalyani	Cum	416.00	184.14	One Hundred EightyFour Paise Fourteen Only
2	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work . Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/ Moorum.(Tipper 5.5 m3) Depth exceeding 1.5m, but not exceeding 3 m	Cum	416.00	177.95	One Hundred SeventySeven Paise NinetyFive Only
3	Supply of water Through water Tank for filling Tank	Each	234.00	324.00	Three Hundred TwentyFour Only
4	Providing Stone dust / Grit 4.75 mm to 0.075 mm to approach road and near immersion tank for levelling and to protect not to sliping	Cum	6.00	900.00	Nine Hundred Only
5	Hire charge of pumping water 3.5 KL/hr capacity Pump	Hr	78.00	37.80	ThirtySeven Paise Eighty Only
6	Providing Causal Labours (Unskilled mazdoor Heavy)	Nos	234.00	392.58	Three Hundred NinetyTwo Paise FiftyEight Only

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike

	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing poles in the ground level for minimum depth of 3.0 mtr and tied with coir rope firmly including cost and conveyance of all materials, labour, lead and lift charges and complete on hire basis as per the engineer in charge.	Mtrs	1236.00	58.50	FiftyEight Paise Fifty Only
8	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 20ft x 30ft = 600 sqft)	Sft	9100.00	7.20	Seven Paise Twenty Only
9	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 13x 18ft = 150 Rft)	Rft	2340.00	15.30	Fifteen Paise Thirty Only
10	Hire Charge for Armless Plastic Chairs	Nos	234.00	3.60	Three Paise Sixty Only
11	Hire Charge for Wooden Table of Size 6ft x 2ft	Nos	65.00	36.00	ThirtySix Only
12	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire	Mtrs	1170.00	8.10	Eight Paise Ten Only
13	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges	Hr	66.00	480.60	Four Hundred Eighty Paise Sixty Only
14	Hire charges for Flood lighting arrangements for the stage and existing immersion Tank during night time	Nos	78.00	256.50	Two Hundred FiftySix Paise Fifty Only
15	Hire charges compoment name 1087 Crane charges	Day	13.00	3051.00	Three Thousand FiftyOne Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,